# WORCESTER COUNTY TECHNICAL REVIEW COMMITTEE AGENDA

Worcester County Government Center, Room 1102, One West Market Street, Snow Hill, Maryland 21863

## August 14, 2019

| Est. Time<br>1:00 P.M. | Ī.   | Call to Order   |  |  |
|------------------------|------|---|--|--|
| 1.00 1                 | ••   |   |  |  |
|                        | II.  | §ZS 1-325 Site Plan Review  |  |  |
| 1:00 P.M.              |      | A. Forefront: Horace & Elwath Solar - Proposed construction of a 2.5 Megawatt (DC) solar photovoltaic facility, located on the northerly side of George Island Landing Road (MD Route 366), west of Portersville Road, Tax Map 94, Parcel 134, Tax District 8, A-1 & A-2 Agricultural Districts, Horace & Elwath LLC, owner/ Forefront Power LLC, applicant/ TRC Companies, Engineer;   |  |  |
| 1:10 P.M.              |      | B. Manklin Station Planned Commercial Development - Proposed construction of Buildings D and E, each consisting of 6,000 square feet of mixed retail/office space within the Manklin Greens PUD and PCD, located on the southerly side of Manklin Creek Road, east of Ocean Parkway, Tax Map 21, Parcel 306, Lot 2, Tax District 3, C-2 General Commercial District, The Holland Island, LLC, owner/ Vista Design, Inc, land planner; |  |  |
| 1:20 P.M.              | III. | Adjourn   |  |  |

\*\*All site plans and plats are available for review during normal business hours, 8 A.M. to 4:30 P.M. in the Department of Development, Review and Permitting, One West Market Street, Room 1201, Snow Hill, MD 21863.\*\*

#### TECHNICAL REVIEW COMMITTEE

X Under the terms of Section ZS 1-325(f)(2), this application is considered to be a major site plan. Ten copies of the revised site plan which address the comments noted within must be submitted to this office no later than 4:30 P.M. on the deadline date. Submittal of an application on or before the deadline date is not a guarantee that the project will be placed on the agenda for the next regularly scheduled Planning Commission meeting. All required preliminary approvals must be obtained no later than 4:30 P.M. on the applicable project confirmation deadline, otherwise the application will not be scheduled. The applicant and specified representatives will be notified by mail of the tentative date and time at which this application will be considered by the Planning Commission on the above date. Should you have any questions regarding the attached comments, please feel free to contact the respective Technical Review Committee member.



DEPARTMENT OF DEVELOPMENT REVIEW AND PERMITTING

## Worcester County

GOVERNMENT CENTER
ONE WEST MARKET STREET, ROOM 1201
SNOW HILL, MARYLAND 21863
TEL:410.632.1200 / FAX: 410.632.3008
http://www.co.worcester.md.us/departments/drp

ADMINISTRATIVE DIVISION CUSTOMER SERVICE DIVISION TECHNICAL SERVICES DIVISION

# WORCESTER COUNTY TECHNICAL REVIEW COMMITTEE August 14, 2019

Jessica Edwards, Customer Service Representative (ext. 1173)

Department of Development, Review and Permitting Worcester County Government Office Building One West Market Street, Room 1201 Snow Hill, MD 21863 (410) 632-1200

Project:

ZONING DIVISION

BUILDING DIVISION

DATA RESEARCH DIVISION

Forefront: Horace & Elwath Solar - Proposed construction of a 2.5 Megawatt (DC) solar photovoltaic facility, located on the northerly side of George Island Landing Road (MD Route 366), west of Portersville Road, Tax Map 94, Parcel 134, Tax District 8, A-1 & A-2 Agricultural Districts, Horace & Elwath LLC, owner/ Forefront Power LLC, applicant/ TRC Companies, Engineer;

#### GENERAL COMMENTS:

- A. In order to obtain a Building Permit, the applicant must submit the following to the Department:
  - 1. Submit a complete Building Permit application, along with the initial fee of \$300.00 made payable to "Worcester County",
  - 2. Submit four (4) sets of complete construction plans (footing, foundation, framing, floor plan and building elevations (front, rear and sides). The construction plans must be sealed by an architect. The plans must be prepared in accordance with the applicable International Building Code, Energy Code, and ADA Code;
  - 3. Submit three (3) sets of the site plan as approved by the Technical Review Committee
- B. Once the permit is issued, the applicant must coordinate all necessary inspections with the respective Building/Housing/Zoning Inspector. The Department requires 24 hour notice for all inspections. The inspector, once on site, may require special or additional inspections than normal.
- C. In order to obtain a Certificate of Use and Occupancy, all of the necessary inspections must be completed and approved by the various inspections agencies (building, zoning, plumbing, electrical, water, sewage, health, roads, etc.). Two sets of As-Builts (illustrating all lighting, landscaping, parking, signs and etc.) must be submitted at least one week prior to the anticipated occupancy of the building, structure or use of land activity. The Department has 48 hours from the last inspection in which to process a Certificate of Use and Occupancy. Please note that it is unlawful to occupy (employees or patrons) a structure without benefit of a Certificate of Use and Occupancy.

Any questions relative to the permit or bonding process should be directed to Jennifer K. Keener at (410) 632-1200, extension 1123.

#### SPECIFIC COMMENTS:

This project is subject to, but not limited to, the following sections of the Zoning and Subdivision Control Article:

| ZS 1-201 | A-1 Agricultural District                                |
|----------|--|
| ZS 1-202 | A-2 Agricultural District                                |
| ZS 1-305 | Lot requirements generally                               |
| ZS 1-306 | Access to structures                                     |
| ZS 1-319 | Access and traffic circulation requirements              |
| ZS 1-322 | Landscaping and buffering requirements                   |
| ZS 1-325 | Site plan review   |
| ZS 1-326 | Classification of highways                               |
| ZS 1-327 | Additional setbacks from drainage ditches and stormwater |
|          | management facilities                                    |
| ZS 1-344 | Alternative Energy Facilities                            |
|          |  |

- 1. According to §ZS 1-344(d)(2), a vegetated buffer at least six feet in width shall be provided within the required yard setback if the panels are located within five hundred feet of any property line zoned or used for residential purposes.
  - a. There appears to be an existing tree line bordering Parcel 136, to the southwesterly property line. If the existing vegetation meets the aforementioned buffering requirements, please add a note on the plans indicating this tree line shall not be disturbed as it is considered part of the necessary buffer. If the tree line does not meet the requirements, it will need to be enhanced in order to meet said requirements.
  - b. In addition, buffering will be necessary within the required setback bordering Parcel 251, Lot 1, as this is a platted residential lot and may be developed as such in the future.
  - c. Additionally, landscaping is required in the side yard setback bordering Portersville Road to the east, as parcels with dwellings exist within five hundred feet of the proposed panels. The proposed landscaping in that area could be repositioned to be within the fifty foot side yard setback and meet the buffering requirements. Please note, relocating the fence is not required to meet these regulations.
- 2. A note was provided on the cover sheet indicating a waiver request to the irrigation requirement. This request will be presented before the Planning Commission at the time of their review.
- 3. Although not a requirement, we would prefer to the adjoining lots be identified with the Tax Map, Parcel and lot (if applicable), instead of, or in addition to, the deed references.
- 4. In accordance with §ZS 1-322(g), a maintenance and replacement bond for required landscaping is mandatory for a period not to exceed two years in an amount not to exceed one hundred and twenty-five percent of the installation cost. A landscape estimate from a nursery will be required to be provided at permit stage to accurately determine the bond amount;
- 5. In accordance with §ZS 1-325(e)(3)O. & P., written confirmation that all water and wastewater requirements have been met will be required to be provided from the Department of Environmental Programs prior to signature approval;
- 6. Approvals will be required from the Dept. of Environmental Programs relative to Forestry and Stormwater Management prior to the Department granting signature approval.
- 7. Comments from the State Highway Administration indicate a District Access Permit will be necessary for the proposed entrance on George Island Landing Road (MD 366).

### **WORCESTER COUNTY TECHNICAL REVIEW COMMITTEE**



Department of Development Review & Permitting
Worcester County Government Center
1 W. Market St., Room 1201
Snow Hill, Maryland 21863
410-632-1200, Ext. 1151
pmiller@co.worcester.md.us

Project: Forefront Solar Project, George Island Landing Road, 2.5 Mw

Date: 8/14/2019

Tax Map: <u>94</u> Parcel: <u>134</u> Section: \_\_\_ Lot: \_\_\_ Block: \_\_\_\_

#### COMMENTS

1. Current Codes: 2015 International Building Code

2017 National Electric Code

Maryland Codes Administration has completed the adoption of the 2018 edition of the International Codes. Worcester County adoption of 2018 I codes is anticipated shortly.

- 2. Wind Design (assumed):116 MPH risk category I; 125 MPH risk category II; Exposure Category "C"; Ground Snow Load 20 PSF
- 3. Soils report required at time of permit application.
- 4. Engineered sealed plans (Maryland) required for all systems and components.
- 5. Special inspector (third party engineer) will be required for all systems and components final certification of project prior to final inspection by building inspector.
- 6. Submit with the permit application the total number and size of solar panels to be in installed.

Additional information may be requested at time of plan review.

Permit fee is by ft<sup>2</sup> of panels x .1131 There is also a fee for fire marshal. **Environmental Programs Division** 

# Memorandum

To: Technical Review Committee (TRC) for August 14, 2019 Meeting

From: Environmental Programs Staff

Subject: Horace & Elwath Solar, SITE PLAN REVIEW,

TM 94 P 134

**Date:** July 29, 2019

Environmental Programs comments are based on the plans submitted. These comments are subject to change every time a change is made to the plans that affect water and/or sewage for this site.

There is no sewage flow attached to this structure and the proposed solar photovoltaic facility is on vacant land; therefore, Environmental Programs has no objection to this request.



LAND PRESERVATION PROGRAMS STORMWATER MANAGEMENT SEDIMENT AND EROSION CONTROL SHORELINE CONSTRUCTION AGRICULTURAL PRESERVATION ADVISORY BOARD

# **ENVIRONMENTAL PROGRAMS**

Worcester County

**GOVERNMENT CENTER** ONE WEST MARKET STREET, ROOM 1306 **SNOW HILL, MARYLAND 21863** TEL:410.632.1220 / FAX: 410.632.2012

WELL& SEPTIC WATER & SEWER PLANNING **PLUMBING & GAS** CRITICAL AREAS FOREST CONSERVATION **COMMUNITY HYGIENE** 

## TECHNICAL REVIEW COMMITTEE FOREST CONSERVATION REVIEW

STAFF PERSON: David Mathers (DM)

145

DATE OF MEETING: August 14, 2019

PROJECT: Forefront: Horace & Elwath Solar

LOCATION: Tax Map 94; Parcel: 134

OWNER: Horace & Elwath, LLC

APPLICANT: Forefront Power, LLC

**ENGINEER: TRC Companies** 

This project is subject to the Worcester County Forest Conservation Law. A Forest Conservation application and review fee have been received. As noted in NR 1-406(d), a concept plan can be used as a substitute to a Forest Stand Delineation because there is not Forest on the site.

According to the site plan submitted, the Net Tract Area (the Limit of Disturbance for agriculturally zoned properties) is 17.7 acres. With an afforestation threshold of 20 percent and conservation threshold of 50 percent, approximately 3.54 acres of afforestation will be required. If afforestation is completed outside the proposed LOD/off-site, the afforestation requirement will need to be provided at a 2:1 ratio, or 7.08 acres. A Forest Conservation Plan and/or off-site mitigation bank utilization agreement must be approved prior to this project being reviewed by the Planning Commission.

This project is subject to the Worcester County Stormwater Ordinance. The project has obtained Stormwater concept plan approval. Site Design Plan approval must be received prior to this case going to the Planning Commission.



DEPARTMENT OF ENVIRONMENTAL PROGRAMS

Worcester County

LAND PRESERVATION PROGRAM STORMWATER MANAGEMENT SEDIMENT AND EROSION CONTROL SHORELINE COSTRUCTION

AGRICULTURAL PRESERVATION

ADVISORY BOARD

GOVERNMENT CENTER
ONE WEST MARKET STREET, ROOM 1306
SNOW HILL, MARYLAND 21863

TEL:410.632.1220 / FAX: 410.632.2012

WELL & SEPTIC
WATER & SEWER PLANNING
PLUMBING & GAS
CRITICAL AREAS/FORESTRY
COMMUNITY HYGIENE

#### **MEMORANDUM**

DATE:

July 18, 2019

TO:

Worcester County Technical Review Committee-

FROM:

Joy S. Birch, Natural Resources Specialist III

RE:

August 14, 2019 Technical Review Committee Meeting

• Forefront: Horace & Elwath Solar – Proposed construction of a 2.5 Megawatt (DC) solar photovoltaic facility, located on the northerly side of George Island Landing Road (MD Route 366), west of Portersville Road, Tax Map 94, Parcel 134, Tax District 8, A-1 & A-2 Agricultural Districts, Horace & Elwath LLC, owner / Forefront Power LLC, applicant / TRC Companies, engineer. This is located outside of the Atlantic Coastal and Chesapeake Bay Critical Area Program. No Comment.



ONE WEST MARKET STREET, ROOM 1003

SNOW HILL, MARYLAND 21863-1194

TEL: 410-632-5666

FAX: 410-632-5664

#### TECHNICAL REVIEW COMMITTEE COMMENTS

PROJECT: Forefront: Horace & Elwath Solar

LOCATION: Tax Map 94; Parcel 134 CONTACT: Horace and Elwath LLC

MEETING DATE: August 14, 2019

TRC #: 2019360

**COMMENTS BY: Matthew Owens** 

**Chief Deputy Fire Marshal** 

As you requested, this office has reviewed plans for the above project. Construction shall be in accordance with applicable Worcester County and State of Maryland fire codes. This review is based upon information contained in the submitted TRC plans only, and does not cover unsatisfactory conditions resulting from errors, omissions or failure to clearly indicate conditions. A full plan review by this office is required prior to the issuance of a building permit. The following comments are noted from a fire protection and life safety standpoint.

#### **Scope of Project**

The proposed construction of a 2.5 megawatt (DC) solar photovoltaic facility.

#### **General Comments**

1. Coordinate 9-1-1 addressing with Worcester County Department of Emergency Services (410) 632-1311.

### **Specific Comments**

- 1. A clear area of 10 feet around ground-mounted photovoltaic installations shall be provided.
- 2. A gravel base or other non-combustible base shall be installed and maintained under and around the installations.
- 3. Fencing, skirting, or other suitable security barriers shall be installed.
- 4. Photovoltaic systems shall be installed in accordance with NFPA 70, *The National Electric Code*.
- 5. Coordinate with the Stockton Volunteer Fire Company regarding the Knox Box.
- 6. No further comments at this time.



# STATE HIGHWAY ADMINISTRATION

Larry Hogan Governor Boyd K. Rutherford Lt. Governor Pete K. Rahn Secretary Gregory Slater Administrator

August 1, 2019

Ms. Jennifer Keener, Zoning Administrator Department of Developing, Review and Planning Worcester County Government Center One West Market Street, Room 1201 Snow Hill MD 21863

Dear Ms. Keener:

Thank you for the opportunity to review the major site plan for Forefront Horace & Elwath Solar, located on the northerly side of MD Route 366 approximately 220 feet from the intersection of MD 366 and Portersville road, in Worcester County. The Maryland Department of Transportation State Highway Administration (MDOT SHA) has reviewed the plans and we are pleased to respond.

This site plan proposes the construction of a 2.5 megawatt (DC) solar photovoltaic facility. After a review of the site plan, we identified a proposed 25 foot wide access onto MD 366, which transitions to a 16 foot wide gravel drive that will be used as a maintenance road for the facility. Based on the limited number of trips generated by the proposed development, a Commercial Access Permit will not be necessary for this entrance; however, a District Access Permit will be required through our Snow Hill Maintenance Shop, located at 5603 Market Street in Snow Hill, Maryland. You may contact the Snow Hill Maintenance Shop by calling 410-632-0511. The shop will provide any guidance necessary to assist you in securing the District Access Permit.

If you have any questions, or require anything additional, please contact Mr. Daniel Wilson, Access Management Regional Engineer, via email at dwilson12@mdot.maryland.gov, or by calling him directly at 410-677-4048. He'll be happy to assist you.

Sincerely.

dames W. Meredith District Engineer

cc: Mr. Hicham Baassiri, District 1 Assistant District Engineer-Project Development, MDOT SHA

Mr. Don Conner, District 1 Access Management Consultant Inspector, MDOT SHA

Mr. Mike Marvel, District 1 Resident Maintenance Engineer, Worcester County, MDOT SHA

Mr. Daniel Wilson, District 1 Access Management Regional Engineer, MDOT SHA



# Morcester County

### DEPARTMENT OF PUBLIC WORKS

6113 TIMMONS ROAD SNOW HILL, MARYLAND 21863

## **MEMORANDUM**

JOHN H. TUSTIN, P.E. DIRECTOR

JOHN S. ROSS, P.E. DEPUTY DIRECTOR

TEL: 410-632-5623 FAX: 410-632-1753 TO:

Jennifer Kenner, Zoning Administrator

FROM:

Frank J. Adkins, Roads Superintendent

DATE: July 29, 2019

SUBJECT: TRC Meeting - August 14, 2019

DIVISIONS

MAINTENANCE TEL: 410-632-3766 PAX: 410-632-1753

\*

ROADS

TEL: 410-632-2244 FAX: 410-632-0020

SOLID WASTE

TEL: 410-632-3177 FAX: 410-632-3000

FLEET MANAGEMENT TEL: 410-632-5675 FAX: 410-632-1753

WATER AND WASTEWATER TEL: 410-641-5251 FAX: 410-641-5185 Section 1-325 Site Plan Review

A. Forefront: Horace & Elwath Solar

1. No comments at this time. Borders State Highway.

**B.** Manklin Station PCD

1. No comments at this time.

cc: John H. Tustin, P.E.

FJA:ll

\\wcfile2\users\llawrence\TRC\2019\8.14.19.doc

#### TECHNICAL REVIEW COMMITTEE

| STAFF PERSON:   |  | Jennifer Keener                       | DATE OF MEETING: _        | August 14, 2019 |  |  |
|---|--|---------------------------------------|---------------------------|-----------------|--|--|
| PROJECT:Manklin Station Planned Commercial Development - Proposed construction of Buildings D and E, each consisting of 6,000 square feet of mixed retail/office space within the Manklin Greens PUD and PCD, located on the southerly side of Manklin Creek Road, east of Ocean Parkway, Tax Map 21, Parcel 306, Lot 2, Tax District 3, C-2 General Commercial District, The Holland Island, LLC, owner/ Vista Design, Inc, land planner;  APPLICANT(S) IN ATTENDANCE: |  |                                       |                           |                 |  |  |
|   |  |                                       |                           |                 |  |  |
|   |  | Keener, Zo                            | oning Administrator       |                 |  |  |
|   |  |                                       | AP Specialist II          |                 |  |  |
|   |  | T T T T T T T T T T T T T T T T T T T | Customer Service Rep.     |                 |  |  |
|   |  | 1071                                  | ilding Plans Reviewer III |                 |  |  |
|   |  |                                       | Environmental Programs    |                 |  |  |
|   |  |                                       | vironmental Programs      |                 |  |  |
|   |  | Bradford,                             | Environmental Programs    |                 |  |  |
|   |  |                                       | rironmental Programs      |                 |  |  |
|   |  | Gerthoffer                            | , Environmental Programs  |                 |  |  |
|   |  |                                       | Environmental Programs    |                 |  |  |
|   |  | Owens, Fi                             |                           |                 |  |  |
|   |  | Adkins, C                             |                           |                 |  |  |
|   |  | Berdan, C                             |                           |                 |  |  |
|   |  |                                       | tate Highway Admin.       |                 |  |  |
|   |  |                                       | tate Highway Admin.       |                 |  |  |
|   |  | Ross, W &                             |                           |                 |  |  |
|   |  | Clayville,                            | Planning Commission Rep   |                 |  |  |

X Under the terms of Section ZS 1-325(f)(2), this application is considered to be a major site plan. Ten copies of the revised site plan which address the comments noted within must be submitted to this office no later than 4:30 P.M. on the deadline date. Submittal of an application on or before the deadline date is not a guarantee that the project will be placed on the agenda for the next regularly scheduled Planning Commission meeting. All required preliminary approvals must be obtained no later than 4:30 P.M. on the applicable project confirmation deadline, otherwise the application will not be scheduled. The applicant and specified representatives will be notified by mail of the tentative date and time at which this application will be considered by the Planning Commission on the above date. Should you have any questions regarding the attached comments, please feel free to contact the respective Technical Review Committee member.



#### DEPARTMENT OF DEVELOPMENT REVIEW AND PERMITTING

# Worcester County

ZONING DIVISION **BUILDING DIVISION** DATA RESEARCH DIVISION

**GOVERNMENT CENTER** ONE WEST MARKET STREET, ROOM 1201 **SNOW HILL, MARYLAND 21863** TEL:410.632.1200 / FAX: 410.632.3008 http://www.co.worcester.md.us/departments/drp

ADMINISTRATIVE DIVISION **CUSTOMER SERVICE DIVISION TECHNICAL SERVICES DIVISION** 

#### WORCESTER COUNTY TECHNICAL REVIEW COMMITTEE

August 14, 2019

Project:

Manklin Station Planned Commercial Development - Proposed construction of Buildings D and E, each consisting of 6,000 square feet of mixed retail/office space within the Manklin Greens PUD and PCD, located on the southerly side of Manklin Creek Road, east of Ocean Parkway, Tax Map 21, Parcel 306, Lot 2, Tax

District 3, C-2 General Commercial District

Prepared by: Jennifer K. Keener, AICP, Zoning Administrator

Contact:

jkkeener@co.worcester.md.us or (410) 632-1200, extension 1123

#### GENERAL COMMENTS:

- A. In order to obtain a Building Permit, the applicant must submit the following to the Department:
  - A complete Building Permit application, along with the initial fee of \$300.00 made payable to "Worcester County";
  - 2. Four (4) sets of complete construction plans, including footing, foundation, framing, floor plan and building elevations - front, rear and sides. The construction plans must be sealed by an architect. The plans must be prepared in accordance with the applicable International Building Code, Energy Code, and ADA Code;
  - Any additional information as requested based upon the scope of the project. The Department will supply copies of the site plan as approved by the Technical Review Committee or the Planning Commission once signature approval has been obtained.
- B. Once the permit is issued, the applicant must coordinate all necessary inspections with the respective Building or Zoning Inspector as outlined on the Inspection Request Form provided at permit issuance. The Department requires 24 hour notice for all inspections. The inspector, once on site, may require special or additional inspections based upon the scope of the project.
- C. In order to obtain a Certificate of Use and Occupancy, all of the necessary inspections must be completed and approved by the various inspections agencies (building, zoning, plumbing, electrical, water, sewage, health, roads, etc.). Two sets of As-Builts (illustrating all lighting, landscaping, parking, signs and etc.) must be submitted at least one week prior to the anticipated occupancy of the building, structure or use of land activity. The Department requires a minimum of 72 hours from the last inspection in order to process a Certificate of Use and Occupancy. Please note that it is unlawful to occupy (employees or patrons) a structure without benefit of a Certificate of Use and Occupancy.

#### SPECIFIC COMMENTS:

This project is subject to, but not limited to, the following sections of the **1992** Zoning and Subdivision Control Article:

| ZS 1-304 | Lot requirements generally                               |
|----------|--|
| ZS 1-305 | Access to structures                                     |
| ZS 1-308 | Off-street parking areas                                 |
| ZS 1-309 | Off-street loading spaces                                |
| ZS 1-325 | Site plan review   |
| ZS 1-326 | PCD planned commercial developments                      |
| ZS 1-332 | Exterior lighting  |
| ZS 1-334 | Landscaping and buffering requirements                   |
| ZS 1-336 | Classification of highways                               |
| ZS 1-337 | Additional setbacks from drainage ditches and stormwater |
|          | management facilities                                    |
| ZS 1-340 | Commercial developments                                  |
| ZS 1-342 | Access and traffic circulation requirements              |
|          |  |

**NOTE:** This project is part of the 1996 Manklin Greens Planned Unit Development, and the 1998 Manklin Station Planned Commercial Development (revised in 2004), both of which were reviewed and approved under the 1992 Zoning and Subdivision Control Article. Therefore, this revision to the site plan for the two remaining buildings illustrated on those plans shall also be reviewed under those standards.

- 1. Please add the following statement with the signature block for the property owner to sign prior to final signature approval: "As the property owner/developer, I am in full agreement with this site plan submitted herewith, and I am responsible for the completion of the improvements as shown on the approved site plan, and I understand that I cannot allow the property or buildings to be occupied until a Certificate of Use and Occupancy has been issued by the Department of Development, Review and Permitting."
- 2. Please note the proposed uses of Buildings D and E on the site plan under the site data;
- 3. Please review the location of the handicap accessible parking spaces and discharge aisles with respect to the column locations. The location of the columns cannot conflict with the depressed curbing that is required for the discharge aisles;
- 4. With respect to the provisions for loading spaces, the original PCD approval illustrated one loading space proposed for Building D, and two proposed for Building E. The current proposal is to eliminate all three, and provide a 9' by 18' area to the rear of Building D.
  - a. Please note that under §ZS 1-326(f)(3), the Planning Commission has the ability to reduce the required loading space requirements by not more than 50% where it is deemed that such a reduced capacity will still meet the needs of the development and the general public. There is one existing loading area to the rear of Building C.
- 5. The proposed site plan illustrates a significant amount of existing trees to be removed

from the parking lot with no plans provided for their replacement.

- a. Please note that a minimum of 1 tree per 10 parking spaces shall be provided, therefore 17 trees shall be provided within the parking lot. An additional 5 trees need to be planted per §ZS 1-334(d)(8)A.;
- b. The remaining landscape islands where trees have been removed shall be planted with shrubs or other landscaping materials per \$ZS 1-334(d)(8)C.;
- 6. Why are the two trees being proposed for removal within the outdoor pedestrian plaza between Buildings B & C?
- 7. Please note the method of irrigation on the plan;
- 8. A maintenance and replacement bond for required landscaping is mandatory for a period not to exceed two years in an amount not to exceed one hundred and twenty-five percent of the installation cost. A landscape estimate from a nursery will be required to be provided at permit stage to accurately determine the bond amount;
- 9. Any on-building signage shall be reviewed and approved at the permit stage based upon tenant fitouts of the buildings;
- 10. While the building plans are not subject to the *Design Guidelines and Standards for Commercial Uses*, the Planning Commission shall review and approve the building elevation design features for consistency with the existing development;
- 11. Written confirmation that the water and sewer requirements have been met will be required to be provided from the Department of Environmental Programs and the Department of Public Works prior to the Department granting signature approval;
- 12. Written confirmation will also be required from the Dept. of Environmental Programs Natural Resources Division relative to Forestry and Stormwater Management requirements prior to the Department granting signature approval. Any preliminary approvals associated with these requirements will need to be addressed as applicable prior to the scheduling of this project for Planning Commission review;
- 13. Written confirmation of approval from the County Roads Division of the Department of Public Works regarding the existing commercial entrances shall be provided to the Department prior to granting signature approval;



#### WORCESTER COUNTY TECHNICAL REVIEW COMMITTEE

Department of Development Review & Permitting Worcester County Government Center 1 W. Market St., Room 1201 Snow Hill, Maryland 21863 410-632-1200, Ext. 1151 pmiller@co.worcester.md.us

\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*\*

Project: Manklin Station, Manklin Creek Road

Date: 8/14/2019

Tax Map: 21 Parcel: 306 Section: Lot: 2

#### STANDARD COMMENTS

- 1. Items listed in this review are <u>not</u> required for Technical Review Committee approval.
- 2. Provide complete code review. List type of construction, use groups, height and area, occupant loads, live, dead and other structural loads.
- 3. Soils report required at time of building permit application.
- 4. Compaction reports due at all footings and slab inspections as well as any site work and structural fill.
- 5. Complete sealed architectural, structural, mechanical, plumbing and electrical plans are required.
- 6. Provide information for wind, snow, floor, roof and seismic loads.
- 7. Special inspections (Third party) required per IBC Chapter 17 for steel, concrete, masonry, wood, prepared fill, foundations and structural observations.
- 8. Provide plan for owner's special inspection program, list inspections and inspection agencies.
- 9. A Maryland Registered Architect must seal plans. This architect or architectural firm will be considered the architect of record.
- 10. A pre-construction meeting will be required before any work starts.
- 11. Provide complete accessibility code requirements and details.
- 12. List on construction documents all deferred submittals.
- 13. Truss and other shop drawings will be required prior to installation. Design professional in responsible charge shall review and approve all shop drawings.
- 14. Please provide your design professional with a copy of these comments.

## Site specific comments

1. Current Codes:

2015 International Building Code

2015 International Residential Code

2015 International Energy Conservation Code

2015 International Mechanical Code

2017 NEC

Maryland Accessibility Code

2010 ADA Standards for Accessible Designs

Maryland Codes Administration has completed the adoption of the 2018 edition of the International Codes. Worcester County adoption of 2018 I codes is anticipated shortly.

- 2. Wind Design: 127 MPH (assumed); Risk category II; Exposure "C"
- 3. Complete sealed architectural, structural, mechanical, plumbing and electrical plans are required for all tenants and tenant fit outs.
- 4. ADA: Provide all details and specifications per 2010 ADA design standards.
- 5. Provide an accessible route from parking to building entrance. Roof columns may not encroach on the accessible route.
- 6. Provide all information per section C103.2 and R103.2: "Information on construction documents of 2015 IECC".
- 7. Provide an Energy Compliance Report and lighting plan (wattage report) for each building.

There is not enough information provided at this time to provide additional comments.

**Environmental Programs Division** 

# Memorandum

To: Technical Review Committee (TRC) for August 14, 2019 Meeting

From: Environmental Programs Staff

Subject: Manklin Station, SITE PLAN REVIEW,

TM 21 P 306 L 2

**Date:** July 29, 2019

Environmental Programs comments are based on the plans submitted. These comments are subject to change every time a change is made to the plans that affect water and/or sewage for this site.

- Reviewing the site plans, there is a slight difference in the square footage of the buildings between the site plans and the architectural plans. This will need to be resolved so we can designate appropriate flow to each building. Manklin Station is allotted 81 EDUs & will be using 3 more EDUs with this proposed project. We will need to make sure that EDUs are assigned correctly. We will also need an EDU chart to be submitted with the next set of site plan
- Natural gas is available to this property.
- Plumbing Code is the 2015 National Standard Plumbing Code (NSPC) Illustrated (National Association of Plumbing-Heating-Cooling Contractors). The Gas Code is National Fuel Gas Code, ANSI Z223.1, NFPA 54, 2015 Edition, for natural gas.
- Commercial Plumbing Plans will need to be submitted for review with each building permit and a \$125 review fee for each submitted. A plumbing permit will be need to be obtained for the interior work and another plumbing permit will be needed for the site utility work. Gas permits will be needed as well, if utilized for this project.



**ENVIRONMENTAL PROGRAMS** 

Worcester County

**GOVERNMENT CENTER** ONE WEST MARKET STREET, ROOM 1306 SNOW HILL, MARYLAND 21863 TEL:410.632.1220 / FAX: 410.632.2012

WELL & SEPTIC WATER & SEWER PLANNING PLUMBING & GAS CRITICAL AREAS FOREST CONSERVATION COMMUNITY HYGIENE

## TECHNICAL REVIEW COMMITTEE FOREST CONSERVATION REVIEW

STAFF PERSON: David Mathers (DW)

LAND PRESERVATION PROGRAMS

SEDIMENT AND EROSION CONTROL

STORMWATER MANAGEMENT

AGRICULTURAL PRESERVATION

SHORELINE CONSTRUCTION

ADVISORY BOARD

DATE OF MEETING: August 14, 2019

PROJECT: Manklin Station Planned Commercial Development

LOCATION: Tax Map 21; Parcel: 306; Lot: 2

OWNER: The Holland Island, LLC

LAND PLANNER: Vista Design, Inc.

This project is exempt from the Worcester County Forest Conservation Law. Under NR 1-403(b)(15), the area of forested non-tidal wetland, including any regulated buffer, is greater than or equal to the area of reforestation and afforestation required.

This project is subject to the Worcester County Stormwater Ordinance. The project has obtained Stormwater concept plan approval. Site Design Plan approval must be received prior to this case going to the Planning Commission.



DEPARTMENT OF ENVIRONMENTAL PROGRAMS

Worcester County

GOVERNMENT CENTER
ONE WEST MARKET STREET, ROOM 1306
SNOW HILL, MARYLAND 21863
TEL:410.632.1220 / FAX: 410.632.2012

WELL & SEPTIC

WATER & SEWER PLANNING
PLUMBING & GAS

CRITICAL AREAS/FORESTRY

COMMUNITY HYGIENE

## **MEMORANDUM**

DATE:

July 18, 2019

TO:

LAND PRESERVATION PROGRAM

SEDIMENT AND EROSION CONTROL

STORMWATER MANAGEMENT

AGRICULTURAL PRESERVATION

SHORELINE COSTRUCTION

ADVISORY BOARD

Worcester County Technical Review Committee

FROM:

Joy S. Birch, Natural Resources Specialist III /

RE:

August 14, 2019 Technical Review Committee Meeting

• Manklin Station Planned Commercial Development – Proposed construction of Buildings D and E, each consisting of 6,000 square feet of mixed retail/office space within the Manklin Greens PUD and PCD, located on the southerly side of Manklin Creek Road, east of Ocean Parkway, Tax Map 21, Parcel 306, Lot 2, Tax District 3, C-2 General Commercial District, The Holland Island, LLC, owner / Vista Design, Inc., land planner. This is located outside of the Atlantic Coastal and Chesapeake Bay Critical Area Program. No Comment.



# STATE HIGHWAY ADMINISTRATION

Larry Hogan Governor Boyd K. Rutherford Lt. Governor Pete K. Rahn Secretary Gregory Slater Administrator

August 1, 2019

Ms. Jennifer Keener, Zoning Administrator Department of Developing, Review and Planning Worcester County Government Center One West Market Street, Room 1201 Snow Hill MD 21863

Dear Ms. Keener:

Thank you for the opportunity to review the major site plan for the proposed Manklin Station Planned Commercial Development, located on the southerly side of Manklin Creek Road, east of Ocean Parkway, in Worcester County, MD. The Maryland Department of Transportation State Highway Administration (MDOT SHA) has reviewed the plans and we are pleased to respond.

This site plan proposes the construction of Buildings D and E, each consisting of 6,000 square feet of mixed retail/office space within the Manklin Greens PUD and PCD. The Construction as proposed is not within the jurisdiction of MDOT SHA, and we do not anticipate the project will negatively impact the surrounding State roadway network. Therefore, the MDOT SHA has no objection to the construction as proposed.

If you have any questions, or require anything additional, please contact Mr. Daniel Wilson, Access Management Regional Engineer, at 410-677-4048, by using our toll free number (in Maryland only) at 1-800-825-4742 (x4048), or via email at dwilson12@mdot.maryland.gov. Mr. Wilson will be happy to assist you.

Sincerely,

James W. Meredith District Engineer

cc: Mr. Hicham Baassiri, District 1 Assistant District Engineer-Project Development, MDOT SHA

Mr. Don Conner, District 1 Access Management Consultant Inspector, MDOT SHA

Mr. Mike Marvel, District 1 Resident Maintenance Engineer, Worcester County, MDOT SHA

Mr. Daniel Wilson, District 1 Access Management Regional Engineer, MDOT SHA



# DEPARTMENT OF PUBLIC WORKS

6113 TIMMONS ROAD Snow Hill, Maryland 21863

## MEMORANDUM

JOHN H. TUSTIN, P.E. DIRECTOR

JOHN S. ROSS, P.E. DEPUTY DIRECTOR

FAX: 410-632-1753

TEL: 410-632-5623

DIVISIONS

MAINTENANCE TEL: 410-632-3766 FAX: 410-632-1753

ROADS TEL: 410-632-2244 FAX: 410-632-0020

SOLID WASTE TEL: 410-632-3177 FAX: 410-632-3000

FLEET MANAGEMENT TEL: 410-632-5675 FAX: 410-632-1753

WATER AND WASTEWATER TEL: 410-641-5251 FAX: 410-641-5185 TO:

Jennifer Kenner, Zoning Administrator

FROM:

Frank J. Adkins, Roads Superintendent

DATE: July 29, 2019

SUBJECT: TRC Meeting – August 14, 2019

## Section 1-325 Site Plan Review

A. Forefront: Horace & Elwath Solar

1. No comments at this time. Borders State Highway.

**B. Manklin Station PCD** 

1. No comments at this time.

cc: John H. Tustin, P.E.

FJA:ll \\wcfile2\users\llawrence\TRC\2019\8.14.19.doc



ONE WEST MARKET STREET, ROOM 1003

SNOW HILL, MARYLAND 21863-1194

TEL: 410-632-5666 FAX: 410-632-5664

#### TECHNICAL REVIEW COMMITTEE COMMENTS

PROJECT: Manklin Station Planned Commercial Development

LOCATION: Tax Map 2126; Parcel 306, Lot 2

CONTACT: The Holland Island, LLC

MEETING DATE: August 14, 2019 COMMENTS BY: Matthew Owens

**Chief Deputy Fire Marshal** 

TRC #: 2019361

As you requested, this office has reviewed plans for the above project. Construction shall be in accordance with applicable Worcester County and State of Maryland fire codes. This review is based upon information contained in the submitted TRC plans only, and does not cover unsatisfactory conditions resulting from errors, omissions or failure to clearly indicate conditions. A full plan review by this office is required prior to the issuance of a building permit. The following comments are noted from a fire protection and life safety standpoint.

#### **Scope of Project**

Proposed construction of building D and E, each consisting of 6000 square feet of mixed retail/office space.

### **General Comments**

- 1. A water supply for fire protection shall be identified indicating the following:
  - a. Water Source
  - b. Engineering study for reliability of water source
  - c. Size (in gallons) of water source
  - d. Replenishment of water supply
  - e. Diameter of in ground pipe
  - f. Number of hydrants
  - g. Location of hydrants
  - h. Roadway width and surface types
  - i. Distance from hydrant to roadway
- 2. If public water source, approved plans by the public works department.
- 3. Water source plans must be approved prior to recording of plat.
- 4. Fire hydrants shall be located within 3 ft. of curb line. Placement of fire hydrants shall be coordinated with this office prior to installation.

Project: Manklin Station Planned Commercial Development

Review #: 2019361

- 5. Obstructions shall not be placed or kept near fire hydrants, fire department inlet connections, or fire protection system control valves in a manner that would prevent such equipment or fire hydrants from being immediately visible and accessible.
- 6. All underground water mains and hydrants **shall be installed, completed, and in service** prior to construction work or as soon as combustible material accumulates, which ever comes first. A stop work order will be issued if fire hydrants are not in service prior to construction work start.
- 7. Adequate emergency turn-a-round shall be provided for all streets in excess of 150 ft with cul-desacs. Cul-de-sacs shall have a minimum centerline radius of 50 ft.
- 8. Roadways shall meet current county roadway standards.
- 9. Fire Lanes shall be provided at the start of a project and shall be maintained throughout construction. Fire lanes shall be not less than 20 ft. in unobstructed width, able to withstand live loads of fire apparatus, and have a minimum of 13 ft. 6 in. of vertical clearance. Fire lane access roadways must be established prior to construction start of any structure in the project. Failure to maintain roadways throughout the project will be grounds to issue stop work orders until the roadway access is corrected.
- 10. Coordinate 9-1-1 addressing with Worcester County Department of Emergency Services (410) 632-1311.

### **Specific Comments**

- 1. Complete set of building plans shall be submitted and approved prior to start of construction.
- 2. Provide and maintain code compliant fire resistance rated separation between all of the tenant spaces.
- 3. Automatic suppression system may be required depending on the intended use of the proposed buildings.
- 4. No further comments at this time.